Heat meter commissioning

Technical brief / Device HM-200 / Revision 2.1

Operating conditions

The maximum operating pressure must not exceed 16 bar.

Maintain a flow rate of 2.5 cubic metres per hour.

Do not disconnect the sensor while the system is pressurized.

Measurement uncertainty: 2% at nominal operating conditions.

Check all electrical connections before commissioning.

Record the serial number and the initial reading.